

Tools Needed:

- 3 Screw guns
 - 2 Robertson bits
 - 1 torx bit
- Prybar

Strike Process:

- Remove Masonite facing by removing screws and using a pry bar for glued sections. Take facing smaller than ½ sheet to dumpster. Save full and half sheets.
- Remove platforms and triscuits from the top of the stud walls using screw guns and the necessary bits – torx for triscuits, Robertson for the other platforms. Take the platforms to the shop to be taken apart and move the triscuits to the stock cart.
- Remove the stud walls from stage floor with screw guns. Take longer stud walls to the shop to be disassembled, bring small stud walls (less than 3' in length) to the dumpster.

Notes:

- Lighting must remove LED strips before platform strike